



FOUNDATION REPAIR BRACKET (UNDERPINNING BRACKET)



REAR VIEW

SCALE: N.T.S.



SIDE VIEW

SCALE: N.T.S.

BRACKET LOAD RATINGS (SEE NOTE-9)		
ANCHOR TYPE	MINIMUM STRENGTH	ULTIMATE STRENGTH
SS5 / SS175	80,000 LB	40,000 LB

BRACKET LOAD RATINGS (SEE NOTE-9)

- DISCLAIMER**
- The information and sketches contained in these drawings are given as guidelines only.
 - Capacities of Chance® Helical Piles may vary depending on, but not limited to, water table elevation and changes to that elevation, changing soil conditions, soil layer thicknesses.
 - Achievable capacities could be higher or lower than ratings due to site-specific conditions. On-site load testing should be performed to confirm additional pile capacities.
 - Installed capacities to be verified by a registered Professional Engineer experienced in Chance® helical pile installation.
 - The information contained herein is to be used for preliminary design activities only, and subject to EBS' Website Disclaimer.

- NOTES**
- HOT DIP GALVANIZE PER ASTM A153-(LATEST REVISION).
 - ASSEMBLED COMPLETE AS SHOWN IN SIDE VIEW.
 - COVERED BY ONE OR MORE OF THE FOLLOWING UNITED STATES PATENTS: 5,011,336 5,120,163 5,213,448
 - DO NOT EXCEED 165 FT-LBS OF TORQUE ON 7/8" DIA LIFTING BOLTS DURING STABILIZING OR LOAD LOCK-OFF.
 - RECOMMENDED ANCHOR SHAFT CUTOFF LEVEL ABOVE THE BOTTOM OF THE FOOTING IS 10" TO 11" FOR MAXIMUM LIFT DISTANCE.
 - FOR DETAILED INSTALLATION INSTRUCTIONS, READ CHANCE BULLETIN 01-9812.
 - MATERIAL SPECIFICATIONS:
BRACKET BODY: PER ASTM A98 AND ASTM A570 GRADE 50.
T-PIPE TUBE: HOT ROLLED MECHANICAL TUBING PER ASTM A500.
 - LIFTING BOLTS: HEX HEAD BOLT PER SAE J429 GRADE 5.
CROSS BOLT: HEX HEAD BOLT PER SAE J429 GRADE 5.
THE C-150-0299 BRACKET HAS A MINIMUM ULTIMATE STRENGTH OF 80,000 LBS. A FACTOR OF SAFETY OF 2 YIELDS A SAFE WORKING LOAD OF 40,000 LBS FOR THE BRACKETS ONLY.
 - THE CAPACITY OF THE UNDERPINNING SYSTEM IS A FUNCTION OF MANY INDIVIDUAL ELEMENTS, INCLUDING THE CAPACITY OF THE FOUNDATION, BRACKET, PILE SHAFT HELICAL PLATE, AND BEARING STRATA, AS WELL AS THE STRENGTH OF THE FOUNDATION TO BRACKET CONNECTION AND THE QUALITY OF PILE INSTALLATION. COLUMN THREE OF THE TABLE SHOWS TYPICAL UNDERPINNING SYSTEM CAPACITIES THAT ARE ACHIEVABLE UNDER NORMAL CONDITIONS. YOUR ACHIEVABLE CAPACITIES COULD BE HIGHER OR LOWER DEPENDING ON THE ABOVE FACTORS.

NO.	DATE	REVISION

EBS
GEOSTEEL

320 Woodlitch Street South, Breslau, Ontario N0B 1M0
Tel: 519-648-3613 Fax: 519-648-2526
Email: info@ebsgeo.com

FOR IHSA

PROJECT: SAMPLE

DRAWING: FOUNDATION REPAIR BRACKET (UNDERPINNING)

DRW'N BY:	SCALE:	N.T.S.
CHECKED:	DATE:	OCTOBER 2021
PROJECT NO.:	DWG. No.:	

TYPICAL INSTALLATION FOUNDATION REPAIR BRACKET

SCALE: N.T.S.

EBS is an authorized distributor of A.B. Chance Civil Construction products.

Since 1912

Registered trademark of A.B. Chance, a division of Hubbell Power Systems, Inc.